




CONCRETE

1. **CONCRETE**— Exterior concrete shall be air-entrained to 4-8%. Admixtures containing calcium chlorides shall not be added to the concrete. Concrete shall have a 28-day strength of 2,000 psi.
2. **REINFORCING BARS**— Reinforcing bars shall conform to ASTM A615, Grade 60. Lap splices shall be 20" in length for #4 bars unless otherwise noted.
3. **REINFORCING MESH**— Welded Wire Fabric (WVF) shall conform to ASTM A185 and shall be lapped a min. of 8" at splices.
4. **CONCRETE SLABS**— Slabs-on-grade shall be built over a 4" layer of #57 stone and over a 6 mil polyethylene vapor barrier, unless otherwise noted.
5. **SUBGRADE FOR FOOTINGS**— Footings shall bear on natural undisturbed soil or tested control fill with a min. allowable bearing capacity of 2000 pounds per sq. ft.
6. **SUBGRADE FOR SLABS**— Slab-on-grade shall bear on natural undisturbed soil or tested control fill with a min. allowable bearing capacity of 2000 pounds per sq. ft. If slabs-on-grade are less than 2'-0" above acceptable undisturbed soil, they may be constructed on up to 2'-0" of self-compacting aggregate, such as #57 stone, in lieu of tested control fill or being designed as structural slabs.
7. **CONCRETE SLAB FINISHES**— Concrete finish shall be Smooth-Trowel Class A (flat within 1/8" in 10'-0") for foundation pad.
8. **CONSTRUCTION**— Sawn crack control joints shall be cut in concrete between 8 and 16 hrs. after concrete is placed.



IT IS THE END USERS RESPONSIBILITY TO HAVE THE ANCHOR-INSTALLATION AND PAD DESIGN DONE BY A PROFESSIONAL ENGINEER.



NOTICE:

THESE FOUNDATION DETAILS ARE ILLUSTRATIVE ONLY, AND SHALL NOT BE USED AS A BASIS FOR CONSTRUCTION OF AN ACTUAL FOUNDATION.

THE ACTUAL FOUNDATION DESIGN, ANCHOR BOLT SIZE, AND EMBEDMENT IS NOT THE RESPONSIBILITY OF SAFETY STORAGE, INC, AND SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER HIRED BY THE OWNER OR CONTRACTOR, AND LICENSED IN THE STATE WHERE THE BUILDING IS TO BE SITED.

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED
A	INITIAL RELEASE	1/10/00	JCG
B	REVISE TEXT, CHAMFER GROUT, PITCH SLAB	10/30/00	JCG
C	REMOVE REF TO UBC ON NOTE #8	02/21/02	JGE
D	REMOVE REF TO NBC ON NOTE #1	05/20/02	JGE
E	REVISE NOTICE NOTE	11/16/04	JGE
F	REVISE ANCHOR NOTE, REMOVE ILLUS SAMPLE	03/30/09	JGE

APPROVALS		DATE	SAFETY STORAGE	
UNLESS OTHERWISE SPECIFIED: ALL DIMENSIONS ARE IN INCHES ± 1"	DRAWN BY: JCG	10/30/00	2301 BERT DRIVE HOLLISTER, CA 95023 PHONE: (408)837-5985 FAX: (408)837-7400	ILLUSTRATIVE SAMPLE FOUNDATION PLAN FOR 1-BOLT BRACKET W/ SET
INTERVALS:	CHECKED BY: B.HALL	10/30/00	MRG SSI	SIZE: DRAWING NO. DA2001F
TW. NUMBER:	MRG SSI			FILE: DA2001F
	NEXT ASSY:			SCALE
	DO NOT SCALE DRAWING			SHEET 1 OF 1

COPYRIGHT © 1996 BY SAFETY STORAGE, INC.
ALL RIGHTS RESERVED
THESE DOCUMENTS ARE NOT TO BE REPRODUCED FOR ANY PURPOSE, IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM SAFETY STORAGE, INC.

